BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule - B

NAME OF THE WORK: Construction of public sitting platform @ Bagalagunte (Near Maramma Temple) & Karekallu) in Bagalagunte in ward no. 14

Sl. No	Description of work	Unit	Qty	Rate quoted by the contractor by sri Ramesh K S	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earth work Excavation for foundation of Buildings, water supply, sanitory lines and electrical conduits either in pits or in trenches 1.5m and above in width. In Hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50m after breaking of clods complete as per the direction of Engineer-in-charge of the work	Cum	34.2	299.0	Rupees Two Hundred Ninety Nine Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost all materials, labour, HOM of machinery, curing complete as per the direction of Engineer-in-charge of the work	Cum	38.43	5100.0	Rupees Five Thousand One Hundred Only
3	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per the direction of Engineer-in-charge of the work	Cum	20.52	4200.0	Rupees Four Thousand Two Hundred Only
4	Providing and constructing granite / trap / basalt size stone masonry in SuperStructure with cement mortar 1:4, edges of stones chistle dresed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per the direction of Engineer-in-charge of the work	Cum	54.72	5900.0	Rupees Five Thousand Nine Hundred Only
5	Filing available Excavated Earth (Excluding Rock) in sides of foundation up to plinth in layers not exceding 20cms in depth, compacting each deposited layer by ramming after watering with lead up to 1.5m. Including cost of materials, labour, curing complete as per the direction of Engineer-in-charge of the work	Cum	34.2	135.0	Rupees One Hundred Thirty Five Only

Executive Engineer
Dasarahalli Division
BBMP

Signature of the Contractor

Ramesh.K.S

6	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per the direction of Engineer-in-charge of the work	Sqm	60.8	103.0	Rupees One Hundred Three Only
7	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite land over existing floor in CM 1:4 at 20mm thick (average) and pointed with white / gey pigment etc., complete using black granite/ Multy Red/ Ruby Red/ Black/ Hassan Green Granite of width not less than 900mm, complete as per the direction of Engineer-in-charge of the work	Sqm	261.5	2400.0	Rupees Two Thousand Four Hundred Only
8	Providing and fixing MS Grill work for windows and ventilators using MS flats or MS square rods, or comination of MS Flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a cost of red lead primer, cost of materials, fixtures, labour and HOM of machinary complete as per the direction of Engineer-in-charge of the work	Kg	2700	82.0	Rupees Eighty Two Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer
Dasarahalli Division
BBMP

Signature of the Contractor